10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any tender quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing four Indian Officers' Quarters, Mysore Transport, Hebbal, Bangalore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation foundation and filling in basement with consolidation	C.yd.	..	71	
2	Granite jelly concrete in lime mortar for foundation in layers of 6″ with tamping	C.ft.	..	654	
3	Size stone in mud foundation with bond stones ..	,,	..	1,480	
4	Burnt stone slabs 6″ thick one line dressed to exposed portion and fixed	S.ft.	..	414	
5	Burnt brick in clay superstructure with proper bonds	C.ft.	..	1,650	
6	Burnt brick in mortar	,,	..	233	
7	Burnt stone slabs 6″ roughly dressed and fixed ..	S.ft.	..	211	
8	T. W. door with panelled shutters and iron fittings ..	,,	..	200	
9	T. W. windows with iron bars and panelled and half glazed shutters	,,	..	98	
10	R.C.C. ornamental ventilators	,,	..	16	
11	Cut stone pillars 9′ height	R.ft.	..	18	
12	R.C.C. 6″ thick roofing with reinforcement 3″ surki concrete 2 courses of flat tiles and plastered on both sides	Sqr.	..	8·17	
13	Plain parapet wall 1½′ high as per design	R.ft.	..	174	
14	Plain cornice alround	,,	..	210	
15	Lime mortar plastering	Sqr.	..	42·01	
16	Cement pointing to basement	,,	..	2·90	
17	White and colour washing two coats	Sqr.	..	42·01	
18	Lac Factory green paint to doors	,,	..	3·46	
19	Flooring with 1½″ cement concrete over 3″ lime concrete finish with red cement and lines cut, etc., complete	,,	..	8·83	
20	Tata's tested steel girders with fixing and hoisting, etc., complete	Cwt.	..	2·09	
21	R.C.C. slab with reinforcement	S.ft.	..	.38	
21*a*	Burnt stone slabs 6″ thick one line dressed for steps ..	,,	..	27	
22	R.C.C. chajja with necessary reinforcement and plastering on both sides	Sqr.	..	4·60	
23	Boxing girders in burnt brick in cement mortar ..	R.ft.	..	18	
24	Rectangular zinc sheet rain water pipe with fixing ..	,,	..	120	
25	Constructing oven and chimney in kitchen and bath	No.	..	2	
26	Providing and fixing pestle and mortar	,,	..	1	
27	Constructing a latrine with R.C.C. slab wall with cement concrete flooring and concrete seats ..	,,	..	1	
28	Constructing drain to lead of kitchen and bath room water to main drain	R.ft.	..	110	

Note—The quantities given above are for constructing one quarter.

M. K. RAJAM IYENGAR,
Executive Engineer.

WATER SUPPLY DIVISION, BANGALORE.

Notification dated 16th February 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, Bangalore, up to 6th April 1940, 3 P.M. for constructing R.C.C. tank of 100,000 gallons capacity near the New Mental Hospital, Bangalore, as per specifications noted below. The work should be completed within three months from the date of acceptance of tender.

2. Tenders should be submitted along with printed specification form which may be obtained from the Executive Engineer on payment of Re. 0-4-0.

3. Each tender must be accompanied by a challan for having credited into the Treasury, a deposit amount of Rs. 750 (Rupees Seven hundred and fifty only) under '17 (*a*) P. W. Deposits' and be superscribed "Tender for constructing R. C. C. tank of 100,000 gallons capacity near the New Mental Hospital, Bangalore City," in default of which tenders will be rejected.

4. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

8. Rates once tendered will not be enhanced on any account.

8. Rates for non-tendered and non-estimated items shall be those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

10. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurement, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

Specifications.

(1) There is at present a circular tank 15′ diameter and 10′ high. A new tank 40′ diameter and 15′ high is to be built concentric with this small existing tank and completely enclosing the same. This is on the ground surface.

(2) The tank should be of R.C.C. and the following factors shall be taken into consideration in the design to be adopted :—

(*a*) Tensile strength of the steel bar—12,000 lbs.
(*b*) While calculating for the circular side walls full bursting pressure shall be considered.
(*c*) The proportion of mixture for all portions except the roof shall be 1 : 1½ : 3 and for the roofing it shall be 1 : 2 : 4.

(3) Suitable dust-proof ventilators should be provided for in the roofing.

(4) The roofing shall be flat with two man-hole covers each 3′ × 3′ complete with mild steel lids with hinges, hasp and stable suitable for locking.

(5) One water level indicator complete with float, gauge board, pointer, flexible wire, guide pulleys, etc., shall be included in the tender.

(6) The outer surface of the side wall should be finished with cream coloured cement.

(7) *Nature of foundation.*—Gravel mixed boulders.

(8) All the pipe fittings will be supplied by the Department.

(9) A small parapet to the tank of suitable design should be provided for in the tender.

(10) No lumpsum quotations will be considered. Plans and estimate with detail drawings showing various reinforcements should accompany the tender. The estimate should give the quantities, rates and cost of each item. Any variation in the quantity will be paid for at the rates as per the detail estimate.

(11) Non-tendered items of work will be paid for after working out the data with not more than 10 per cent profit for the contractor.

(12) Cement to be used should be purchased through the Department.

M. K. NARASIMHA IYER,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 16th March 1940.

The attention of the public is invited to the notification published on pages 492—498, Part VI of the *Mysore Gazette*, dated 7th March 1940, calling for tenders for the work of constructing Dispensary Buildings at Bukkambudi, Tarikere Taluk.

The last date of receipt of tender in this office is extended to 3 P.M. on 2nd April 1940, instead of 16th March 1940, as notified in the original notification.

M. A. RAMANUJAM,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE.

OFFICE OF THE AGRICULTURAL ENGINEER, BANGALORE.

Notification No. 11 *of* 1939-40, *dated 12th March* 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Agricultural Engineer, up to 2 P.M. on 6th April 1940 for constructing a Tobacco Curing Barn on the Hebbal Farm.